			Rs.	a.	p.
24	On every horse, if laden or ridden		0	1	6
25	Do do if unladen or led		0	0	9
26	Do tattu or mule, if laden or ridden		0	0	9
27	Do do if unladen or led		0	0	6
28	Do ass, if laden or ridden		0	0	6
29	Do ass, if unladen or led		0	0	3
30	Do sheep, goat or pig		0	0	1
31	Do palanquin, dholi, palna or tanjan with two bearers		0	2	0
32	Do do do with more than two bearers		0	4	0

N.B.—Animals drawing any vehicle for which toll can be demanded are not also to be charged with toll.

B. T. KESAVIENGAR,
Deputy Commissioner.

OFFICE OF THE PRESIDENT, DISTRICT BOARD, HASSAN.

Dated 20th January 1928.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Hassan, up to 2 P.M., on 1st February 1928, for constructing a tunnel near Settihalli across the Ankanahalli Gundihalla on the Settihalli Gorur cart track. An approximate estimate of quantities is given below. The quantities are not guaranteed. The work should be completed by the end of May 1928.

2. The plan, detailed estimate and conditions may be seen at the President's Office at Hassan between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of rupees one hundred (Rs. 100) only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a tunnel near Settihalli in Gorur cart-track" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board Hassan, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the Notice Board in the President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of probable quantity.

Particulars	Per	Rate	Quantity	Cost	Total
		Rs. a. p.		Rs.	Rs.
1. Earthwork excavation	C.yd.		274		
2. Concrete in surki mortar	C.ft.		2,241		
3. Burnt brick in surki mortor	,,		4,860		
4. Burnt stone slabs 6″ dressed... ...	S.ft.		1,111		
5. Plastering with surki mortor ...	Sqr.		30·92		
6. Fixing guard stones 3′ x 1½′	No.		4		
7. Cornice work 9″ thick	R.ft.		106½		
8. Rough stone work new to sides ...	C.yd.		107		
9. Forming approaches and metalling over the tunnel.	L. S.				
10. Bailing water and blasting boulders ..	L. S.				
11. Contingencies	...				

N. S. NANJUNDIAH,
President.